## **CONCRETE TEST REPORT**

TO ABC ENGINEERING LTD. **545 SYCAMORE WAY** WINDY CITY, AB

**PROJECT NAME: Local Business** 

Complex

SCOPE:

**MATERIAL TESTING** 

SAMPLE	ТҮРЕ	CURE LOC.	TEST DATE	AGE (DAYS)	AVG. DIAMETER (mm)	AVG. LENGTH (mm)	MAX. LOAD (kN)	COMPRESSIVE STRENGTH (MPa)	FRACTURE TYPE
Α	Cylinder	Lab	2021-07-18	7	101.6	203.2	270	33.4	b
В	Cylinder	Lab	2021-08-08	28	101.6	203.2	430	53.1	b
С	Cylinder	Lab	2021-08-08	28	101.6	203.2	504	62.2	b
D	Cylinder	Lab	2021-09-05	56	101.6	203.2	521	64.3	С

SPEC. STREN	GTH	55	MPa	@	56	DAYS	
CEMENT TYP	E					GU/GUL	
SCM CONTEN MAXIMUM SIX BATCH TIME ADMIXTURES	ZE AGO	1	14 2:12	FLY ASH mm			
SUPER-P JAZZ					1	DOSE	
SUPPLIER	TOP	CONC	RETE				

LTD.

MIX NO. KJF93390

TRUCK NO. 156 **TICKET** 88801

NO. LOAD VOL. 16 m3 **WATER ADDED AUTH** 

24.0 °C **AIR TEMP.** 23.0 °C CONCRETE TEMP. 180 mm SPEC. SLUMP 190 mm SLUMP **SLUMP FLOW SPEC. FLOW** 

NA mm **AIR CONTENT** 1.2 %

**CAST TIME** 13:05

**CAST DATE** 2021-07-11 **CAST BY** CMF

LOCATION

L07, GL D2, E2, D3, E3

**COMMENTS** 

PREPARED BY SOME COMPANY

BY TECH INITIALS