## **CONCRETE TEST REPORT**

TO ABC ENGINEERING LTD.
545 SYCAMORE WAY
WINDY CITY, AB

PROJECT NAME: Local Business

Complex

**SCOPE:** MATERIAL TESTING

SAMPLE	ТҮРЕ	CURE LOC.	TEST DATE	AGE (DAYS)	AVG. DIAMETER (mm)	AVG. LENGTH (mm)	MAX. LOAD (kN)	COMPRESSIVE STRENGTH (MPa)	FRACTURE TYPE
Α	Cylinder	Lab	2021-04-11	7	101.6	203.2	285	35.2	b
	Cylinder	Lab			101.6	203.2			b
	Cylinder	Lab			101.6	203.2			b
	Cylinder	Lab			101.6	203.2			С

SPEC. STRENGTH	55	MPa	@ 56	DAYS	CONCRETE TEMP. 24.0 °C AIR TEMP. 23.0 °C SLUMP 180 mm SPEC. SLUMP 190 mm
CEMENT TYPE				GU/GUL	SLUMP FLOW NA mm SPEC. FLOW 1.2 %
SCM CONTENT MAXIMUM SIZE A BATCH TIME ADMIXTURES SUPER-P JAZZ	GGREGA	TE	14 12:12 1	FLY ASH mm	CAST TIME 13:05 CAST DATE 2021-04-04 CAST BY CMF  LOCATION L02, GL B2, B3, C1, C2, C3 COMMENTS
	OP CONC TD.	RETE			
-	JF93390 86		TICKET NO.	69542	
LOAD VOL. WATER ADDED			16 m3 <b>AUTH</b>		
					PREPARED BY SOME COMPANY
					BY TECH INITIALS