## **CONCRETE TEST REPORT**

TO ABC ENGINEERING LTD.
545 SYCAMORE WAY
WINDY CITY, AB

**PROJECT NAME:** Local Business

Complex

SCOPE:

MATERIAL TESTING

SAMPLE	ТҮРЕ	CURE LOC.	TEST DATE	AGE (DAYS)	AVG. DIAMETER (mm)	AVG. LENGTH (mm)	MAX. LOAD (kN)	COMPRESSIVE STRENGTH (MPa)	FRACTURE TYPE
А	Cylinder	Lab	2021-05-28	7	101.6	203.2	276	34.1	b
В	Cylinder	Lab	2021-06-18	28	101.6	203.2	424	52.3	b
С	Cylinder	Lab	2021-06-18	28	101.6	203.2	423	52.2	b
	Cylinder	Lab			101.6	203.2			С

SPEC. STRENGT	ГН !	55	MPa	@	56	DAYS	CONCRETE TEN	<b>ИР.</b> 180	24.0 mm	°C AIR TEMP. SPEC. SLUMP	23.0 190	°C mm
CEMENT TYPE						GU/GUL	SLUMP FLOW AIR CONTENT	NA 1.2	mm %	SPEC. FLOW		
SCM CONTENT MAXIMUM SIZE BATCH TIME ADMIXTURES SUPER-P JAZZ	AGGR	EGA	TE		14 12:12 1	FLY ASH mm	CAST TIME CAST DATE LOCATION L03, GL C4, C5, COMMENTS		05-21	CAST BY	CMF	
SUPPLIER MIX NO. TRUCK NO. LOAD VOL. WATER ADDED	TOP CO LTD. KJF933 136		RETE	<b>N</b> 0	_	32890						
							PREPARED BY SO		MPANY			