## **CONCRETE TEST REPORT**

TO ABC ENGINEERING LTD.
545 SYCAMORE WAY
WINDY CITY, AB

**PROJECT NAME:** Local Business **SCOPE:** MATERIAL TESTING

Complex

SAMPLE	ТҮРЕ	CURE LOC.	TEST DATE	AGE (DAYS)	AVG. DIAMETER (mm)	AVG. LENGTH (mm)	MAX. LOAD (kN)	COMPRESSIVE STRENGTH (MPa)	FRACTURE TYPE
А	Cylinder	Lab	2021-08-01	7	101.6	203.2	303	37.4	b
В	Cylinder	Lab	2021-08-22	28	101.6	203.2	473	58.4	b
С	Cylinder	Lab	2021-08-22	28	101.6	203.2	505	62.3	b
	Cylinder	Lab			101.6	203.2			С

SPEC. STRENGT	Ή	55	MPa	@	56	DAYS	CONCRETE TEI		24.0 mm		AIR TEMP. C. SLUMP	23.0 190	_
CEMENT TYPE						GU/GUL	SLUMP FLOW AIR CONTENT	1.2	, -	SPEC	. FLOW		
SCM CONTENT MAXIMUM SIZE BATCH TIME ADMIXTURES	AGGI	REGA	TE		14 12:12	FLY ASH mm	CAST TIME CAST DATE		07-25	CAS1	Г <b>В</b> Ү	CMF	
SUPER-P JAZZ					1	DOSE	L08, GL C4, C5, COMMENTS	E4, E5					
SUPPLIER MIX NO. TRUCK NO. LOAD VOL. WATER ADDED	TOP ( LTD. KJF93 132			<b>N</b> 0	0.	11635							
							PREPARED BY SO BY TECH INITIAL		MPANY				