CONCRETE TEST REPORT

TO ABC ENGINEERING LTD.
545 SYCAMORE WAY
WINDY CITY, AB

PROJECT NAME: Local Business **SCOPE:** MATERIAL TESTING

Complex

SAMPLE	ТҮРЕ	CURE LOC.	TEST DATE	AGE (DAYS)	AVG. DIAMETER (mm)	AVG. LENGTH (mm)	MAX. LOAD (kN)	COMPRESSIVE STRENGTH (MPa)	FRACTURE TYPE
Α	Cylinder	Lab	2021-06-08	7	101.6	203.2	175	21.7	b
В	Cylinder	Lab	2021-06-29	28	101.6	203.2	319	39.4	b
С	Cylinder	Lab	2021-06-29	28	101.6	203.2	289	35.7	b
	Cylinder	Lab			101.6	203.2			С

SPEC. STRENGT	ГН	35	MPa	@	28	DAYS	CONCRETE TEN		24.0 mm	°C AIR TEN		°C mm
CEMENT TYPE						GU/GUL	SLUMP FLOW AIR CONTENT	NA 1.2		SPEC. FLOW	1	
SCM CONTENT MAXIMUM SIZE BATCH TIME ADMIXTURES SUPER-P JAZZ	AGGI	REGA	TE		14 12:12 1	FLY ASH mm	CAST TIME CAST DATE LOCATION L04, E Slab COMMENTS	13:05 2021-	06-01	CAST BY	CMF	
SUPPLIER MIX NO. TRUCK NO. LOAD VOL. WATER ADDED	TOP (LTD. KJF83 138		RETE	N 0		80552	COMMENTS					
						PREPARED BY SC BY TECH INITIALS		MPANY				