CONCRETE TEST REPORT

TO ABC ENGINEERING LTD.
545 SYCAMORE WAY
WINDY CITY, AB

PROJECT NAME: Local Business

Complex

SCOPE: MATERIAL TESTING

SAMPLE	ТҮРЕ	CURE LOC.	TEST DATE	AGE (DAYS)	AVG. DIAMETER (mm)	AVG. LENGTH (mm)	MAX. LOAD (kN)	COMPRESSIVE STRENGTH (MPa)	FRACTURE TYPE
Α	Cylinder	Lab	2021-06-25	7	101.6	203.2	242	29.9	b
В	Cylinder	Lab	2021-07-16	28	101.6	203.2	353	43.6	b
С	Cylinder	Lab	2021-07-16	28	101.6	203.2	351	43.4	b
	Cylinder	Lab			101.6	203.2			С

SPEC. STRENGT	Н	45	MPa	@	28	DAYS	CONCRETE TEN	ИР. 180	_	°C AIR TEMP. SPEC. SLUMP		°C mm
CEMENT TYPE						GU/GUL	SLUMP FLOW AIR CONTENT	NA 1.2	, -	SPEC. FLOW		
SCM CONTENT MAXIMUM SIZE BATCH TIME ADMIXTURES SUPER-P JAZZ	AGG	REGA	ATE		14 2:12 1	FLY ASH mm	CAST TIME CAST DATE LOCATION L05, Shear walls COMMENTS		06-18	CAST BY	CMF	
	TOP (LTD. KJF93 112	CONC 3390		NO.	m3	68263						
							PREPARED BY SO		MPANY			