CONCRETE TEST REPORT

TO ABC ENGINEERING LTD. 545 SYCAMORE WAY WINDY CITY, AB

PROJECT NAME: Local Business SCOPE: MATERIAL TESTING

Complex

SAMPLE	ТҮРЕ	CURE LOC.	TEST DATE	AGE (DAYS)	AVG. DIAMETER (mm)	AVG. LENGTH (mm)	MAX. LOAD (kN)	COMPRESSIVE STRENGTH (MPa)	FRACTURE TYPE
Α	Cylinder	Lab	2021-05-17	7	101.6	203.2	209	25.8	b
В	Cylinder	Lab	2021-06-07	28	101.6	203.2	405	50.0	b
С	Cylinder	Lab	2021-06-07	28	101.6	203.2	360	44.5	b
	Cylinder	Lab			101.6	203.2			С

SPEC. STRENGT	ГН	45	MPa	@	28	DAYS	CONCRETE TEN	1P. 180	24.0 mm	°C AIR TEMP. SPEC. SLUMP		°C mm
CEMENT TYPE						GU/GUL	SLUMP FLOW AIR CONTENT	NA 1.2	mm %	SPEC. FLOW		
SCM CONTENT MAXIMUM SIZE BATCH TIME ADMIXTURES SUPER-P JAZZ	: AGG	REG <i>A</i>	ATE		14 2:12 1	FLY ASH mm	CAST TIME CAST DATE LOCATION L02, Shear walls COMMENTS	-	05-10	CAST BY	CMF	
SUPPLIER MIX NO. TRUCK NO. LOAD VOL. WATER ADDED	TOP (LTD. KJF93 131		RETE	TIC NO. 16 I	m3	86652						
							PREPARED BY SC BY TECH INITIALS		MPANY			