CONCRETE TEST REPORT

TO ABC ENGINEERING LTD.
545 SYCAMORE WAY
WINDY CITY, AB

PROJECT NAME: Local Business **SCOPE:** MATERIAL TESTING

Complex

SAMPLE	ТҮРЕ	CURE LOC.	TEST DATE	AGE (DAYS)	AVG. DIAMETER (mm)	AVG. LENGTH (mm)	MAX. LOAD (kN)	COMPRESSIVE STRENGTH (MPa)	FRACTURE TYPE
Α	Cylinder	Lab	2021-08-16	7	101.6	203.2	214	26.5	b
	Cylinder	Lab			101.6	203.2			b
	Cylinder	Lab			101.6	203.2			b
	Cylinder	Lab			101.6	203.2			С

SPEC. STRENGT	ГН	45	MPa	@	28	DAYS	CONCRETE TEI		24.0 mm	°C AIR TEM SPEC. SLUMI		°C mm
CEMENT TYPE						GU/GUL	SLUMP FLOW AIR CONTENT	NA 1.2		SPEC. FLOW		
SCM CONTENT MAXIMUM SIZE BATCH TIME	AGG	REGA	TE		l4 !:12	FLY ASH mm	CAST TIME CAST DATE LOCATION	13:05 2021-		CAST BY	CMF	
ADMIXTURES SUPER-P JAZZ					1	DOSE	L09, Shear walls	on GL	1, GL E			
SUPPLIER MIX NO. TRUCK NO. LOAD VOL. WATER ADDED	TOP LTD. KJF93 118			TICK NO. 16 m AUT	n3	58761						
							PREPARED BY SO		MPANY			