CONCRETE TEST REPORT

TO ABC ENGINEERING LTD. 545 SYCAMORE WAY WINDY CITY, AB

PROJECT NAME: Local Business

Complex

NO.

16 m3

AUTH

LOAD VOL.

WATER ADDED

SCOPE:

MATERIAL TESTING

°C mm

SAMPLE	ТҮРЕ	CURE LOC.	TEST DATE	AGE (DAYS)	AVG. DIAMETER (mm)	AVG. LENGTH (mm)	MAX. LOAD (kN)	COMPRESSIVE STRENGTH (MPa)	FRACTURE TYPE
Α	Cylinder	Lab	2021-07-18	7	101.6	203.2	270	33.4	b
В	Cylinder	Lab	2021-08-08	28	101.6	203.2	430	53.1	b
С	Cylinder	Lab	2021-08-08	28	101.6	203.2	504	62.2	b
	Cylinder	Lab			101.6	203.2			С

SPEC. STRENG	TH 55	MPa	@ 56	DAYS	CONCRETE TEMP.		24.0 °0	C AIR TEMP.	23.0 190
CEMENT TYPE				GU/GUL	AIR CONTENT	1.2 %		SPEC. FLOW	
SCM CONTENT MAXIMUM SIZE AGGREGATE BATCH TIME ADMIXTURES		14 12:12	FLY ASH mm		3:05)21-07-	-11 C	CAST BY	CMF	
SUPER-P JAZZ			1	DOSE	COMMENTS	LJ			
SUPPLIER	TOP CON- LTD.								
MIX NO. TRUCK NO.	KJF93390 156		TICKET	88801					

PREPARED BY SOME COMPANY

BY TECH INITIALS