CONCRETE TEST REPORT

TO ABC ENGINEERING LTD.
545 SYCAMORE WAY
WINDY CITY, AB

PROJECT NAME: Local Business

Complex

SCOPE:

MATERIAL TESTING

SAMPLE	ТҮРЕ	CURE LOC.	TEST DATE	AGE (DAYS)	AVG. DIAMETER (mm)	AVG. LENGTH (mm)	MAX. LOAD (kN)	COMPRESSIVE STRENGTH (MPa)	FRACTURE TYPE
Α	Cylinder	Lab	2021-05-06	7	101.6	203.2	284	35.1	b
В	Cylinder	Lab	2021-05-27	28	101.6	203.2	428	52.9	b
С	Cylinder	Lab	2021-05-27	28	101.6	203.2	466	57.5	b
D	Cylinder	Lab	2021-06-24	56	101.6	203.2	468	57.8	С

SPEC. STRENGT	H 55	MPa	@ 56	DAYS	CONCRETE TEMP. 24.0 °C AIR TEMP. 23.0 °C SLUMP 180 mm SPEC. SLUMP 190 mm
CEMENT TYPE				GU/GUL	SLUMP FLOW NA mm SPEC. FLOW AIR CONTENT 1.2 %
SCM CONTENT MAXIMUM SIZE BATCH TIME ADMIXTURES SUPER-P JAZZ	AGGREG	ATE	14 12:12 1	FLY ASH mm	CAST TIME 13:05 CAST DATE 2021-04-29 CAST BY CMF LOCATION L04, GL A1, A2, A'1, A'2, B1
SUPPLIER	TOP CON	CRETE	1	DOSE	COMMENTS
MIX NO. TRUCK NO.	KJF93390 194		TICKET NO.	32101	
LOAD VOL. WATER ADDED			16 m3 AUTH		
					PREPARED BY SOME COMPANY
					BY TECH INITIALS