## **CONCRETE TEST REPORT**

TO ABC ENGINEERING LTD.
545 SYCAMORE WAY
WINDY CITY, AB

PROJECT NAME: Local Business

Complex

**SCOPE:** MATERIAL TESTING

SAMPLE	ТҮРЕ	CURE LOC.	TEST DATE	AGE (DAYS)	AVG. DIAMETER (mm)	AVG. LENGTH (mm)	MAX. LOAD (kN)	COMPRESSIVE STRENGTH (MPa)	FRACTURE TYPE
Α	Cylinder	Lab	2021-06-01	7	101.6	203.2	292	36.1	b
В	Cylinder	Lab	2021-06-22	28	101.6	203.2	466	57.5	b
С	Cylinder	Lab	2021-06-22	28	101.6	203.2	481	59.4	b
D	Cylinder	Lab	2021-07-20	56	101.6	203.2	500	61.7	С

SPEC. STRENGT	<b>'H</b> 55	MP	<b>a</b> @	56	DAYS	CONCRETE TEMP.         24.0 °C         AIR TEMP.         23.0 °C           SLUMP         180 mm         SPEC. SLUMP         190 mm
CEMENT TYPE					GU/GUL	SLUMP FLOW NA mm SPEC. FLOW AIR CONTENT 1.2 %
SCM CONTENT MAXIMUM SIZE BATCH TIME ADMIXTURES SUPER-P JAZZ	AGGRE	GATE		14 12:12 1	FLY ASH mm	CAST TIME 13:05 CAST DATE 2021-05-25 CAST BY CMF  LOCATION L06, GL A1, A2, A'1, A'2, B1 COMMENTS
SUPPLIER MIX NO. TRUCK NO. LOAD VOL. WATER ADDED	TOP COI LTD. KJF9339 134		T N 16	ICKET IO. m3 .UTH	13230	
						PREPARED BY SOME COMPANY BY TECH INITIALS