CONCRETE TEST REPORT

TO ABC ENGINEERING LTD.
545 SYCAMORE WAY
WINDY CITY, AB

PROJECT NAME: Local Business

Complex

SCOPE: MATERIAL TESTING

SAMPLE	ТҮРЕ	CURE LOC.	TEST DATE	AGE (DAYS)	AVG. DIAMETER (mm)	AVG. LENGTH (mm)	MAX. LOAD (kN)	COMPRESSIVE STRENGTH (MPa)	FRACTURE TYPE
Α	Cylinder	Lab	2021-08-14	7	101.6	203.2	257	31.8	b
В	Cylinder	Lab	2021-09-04	28	101.6	203.2	448	55.3	b
С	Cylinder	Lab	2021-09-04	28	101.6	203.2	460	56.8	b
	Cylinder	Lab			101.6	203.2			С

SPEC. STRENGT	ГН	55	MPa	@	56	DAYS	CONCRETE TE		24.0 mm	_	AIR TEMP. . SLUMP		°C mm
CEMENT TYPE						GU/GUL	SLUMP FLOW AIR CONTENT	1.2		SPEC	. FLOW		
SCM CONTENT MAXIMUM SIZE BATCH TIME ADMIXTURES SUPER-P JAZZ	AGG	REGA	ΙΤΕ		14 12:12 1	FLY ASH mm	CAST TIME CAST DATE LOCATION L09, GL C4, C5, COMMENTS	-	08-07	CAST	ВҮ	CMF	
SUPPLIER MIX NO. TRUCK NO. LOAD VOL. WATER ADDED	TOP (LTD. KJF93 114	CONC 3390	RETE	16	TICKET IO. m3 AUTH	28298							
							PREPARED BY SO		MPANY				